ENGINEERING DEPARTMENT.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification, dated 8th March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 1st April 1933, for laying and jointing the pumping and distribution mains of water-supply to Dodballapur Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Sanitary Engineer's Office, between the hours of 11 A.M. to 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash as earnest money, and be superscribed " Tender for laying and jointing the pumping and distribution mains of Water Supply to Dodballapur Town " in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Executive Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual Contract Bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Sanitary Engineer, after working our data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Abstract estimate of quantities of work to be done.

Sl. No.	Particulars	Unit	Quantity
	I. Laying and Jointing the 3" and 4" C. I. Pumping Main from No. 3 Borewell to Elevated Tank.		
1	Earthwork excavating, refilling, watering, tamping pipe trench	C. yd.	987
2	Blasting and cutting rock, if any, along the pipe trench, refilling, watering and tamping complete.	"	100
3	Conveying, laying and jointing with lead or rubber insertions and bolts and nuts for flanged joints including cuts and collar joints of 4" C.I.	Joint	240
4	Do do 3" C.I. ...	"	100
5	Constructing valve cisterns 3' x 3' as per plan ...	Each	5
6	Conveying and fixing the C. I. valve cistern shutters 2½' x 2' with necessary bolts and nuts drilling holes in slabs complete.	"	5
	II. Laying and Jointing the 3" C. I. Pumping Main from No. 4 Borewell to the Elevated Tank.		
1	Earthwork excavating, refilling, watering and tamping pipe trench.	C.yd.	542
2	Blasting and cutting hard rock along the pipe trench, refilling, watering and forming complete.	"	Say 50
3	Conveying, laying and jointing with lead or rubber insertions and bolts and nuts for flange joints, including cuts and collar joints of 3" C. I.	Joint	240
4	Constructing 3' x 3' valve cisterns as per plan	Each	5

Sl. No.	Particulars	Unit	Quantity
	III. Laying and Jointing the Town Distribution System.		
1	Earthwork excavation pipe trench for 3" C. I. pipe line, including refilling, watering and tamping complete.	C.yd.	425
2	Cutting or blasting hard rock along the pipe line, refilling, watering and tamping complete.	,,	Say 15
3	Conveying, laying and jointing with lead or rubber insertions and bolts and nuts for flange joints for 3" C. I. pipes and specials.	Joint	160
4	Earthwork, laying and jointing the 1½' G. I. pipes and specials, including cutting and threading complete.	R.ft.	785
5	Do ¾" G. I. pipes and specials ..	Each	260
6	Constructing valve cisterns of 3' x 3' as per plan ..	,,	1
7	Constructing 1½' x 1½' x 1½' gland cock cisterns and fixing road boxes.	,,	9
8	Constructing public tap platforms with slab uprights and edge slabs of size 4' x 4' as per plan.	,,	14

Abstract Notification.

The attention of the public is invited to the Notice calling for tenders, for "Laying Street Sewers to be connected to Submain Sewer No. 2; passing along Balepet to Sultanpet, Bangalore City," published on pages 257 and 258, Part VI of the *Mysore Gazette*, dated 9th March 1933. The last date for receipt of tenders is 28th March 1933.

B. R. GARUDACHAR,
Executive Sanitary Engineer.

BANGALORE BUILDINGS DIVISION, BANGALORE.

"Notification dated 1st March 1933."

Government having in their order No. P. W. 1795—1811-3, dated 31st January 1933 sanctioned the conversion of the office of the Head Quarter Range, Bangalore into "Buildings Division, Bangalore," all communications intended for the Range Office, will hereafter be addressed to the Executive Engineer, Bangalore Buildings Division, Bangalore.

A. TANDONI RAO,
Executive Engineer.

BANGALORE DIVISION.

Notification dated 7th March 1933.

Notice is hereby given that sealed quotations will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 29th March 1933, for, "Constructing Urdu Middle School Building at Dodballapur." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division, Bangalore, between the hours of 11 A.M. and 5 P.M. on all office days.